

ADDENDUM NO. TWO

To the Plans and Specifications for:  
Safety Deficiencies Renovation at Baseball and  
Softball Fieldhouses at  
Wolfson High School, No. 224

Prepared By:

**ARCHITECT**

Bhide & Hall Architects, P.A.  
1329-C Kingsley Avenue  
Orange Park, FL 32073  
Certificate No. AAC000569

**MECHANICAL/ELECTRICAL**

Haddad Engineering Inc.  
3030 Hartley Road, Suite 290  
Jacksonville, FL 32257  
Certificate No. 4000

Date: May 19, 2020

NOTE: An entire set of plans is included with this Addendum  
(20 sheets total)

**Index:**

<b><u>No.</u></b>	<b><u>Discipline</u></b>	<b><u>Topic</u></b>
1	Architectural	Fire Extinguishers
2	Architectural	Fire Alarm Devices
3	Architectural	Signage
4	Architectural	Life Safety Plan – Travel Distances
5	Architectural	New Doors
6	Architectural	Demolition Plan
7	Architectural	Handrail and Concrete Work at Buildings 9 & 10
8	Architectural	General Notes
9	Architectural	Trench Drain
10	Mechanical	HVAC Floor Plan
11	Electrical	Emergency Lighting

11 ITEMS TOTAL

---

**ARCHITECTURAL**

**Item No.1 Fire Extinguishers**

- a. Refer to attached, revised Sheet LS-1. Fire extinguishers have been added to Building 10, Rooms 103 and 105B.
- b. Plans indicate 2 fire extinguishers in Building 11, Room 101. Delete one extinguisher in this room.
- c. Add fire extinguisher note on Sheet LS-1.

**Item No.2 Fire Alarm Devices**

Refer to attached, revised sheet LS-1. Two fire alarm strobe devices are shown in Office 110. Remove one device for consistency with Electrical Sheet E3.1.

**Item No.3 Signage**

Specifications. Section 10440. Revise paragraph 2 to read,

“2. Products

2.1 Sign Types

- a. An informational sign with Braille is required at the Concessions Building No. 9. Refer to detail 7/A5.1 for text. Sign shall be red background with 1" white letters.
- b. Tactile Exit Signs, nominally 6" wide x 4" tall with 1 ½" text, red background with white letters, including Braille. Locate at each door exit.
- c. An information sign with Braille is required at Building 10, Room 104, “STORAGE OF FLAMMABLE MATERIALS IS PROHIBITED IN THIS ROOM”. Sign shall be red background with 1 ½" white letters. Refer also to Sheet LS-1.
- d. Provide two maximum capacity signs with Braille in Building 10, Room 201. Sign shall read, “MAXIMUM CAPACITY 45 OCCUPANTS”. Sign shall be red background with 1 ½ " white letters. Install signs at each exit door. Refer also to Sheet LS-1.
- e. Provide signage reading, “CAUTION HAZARDOUS STORAGE” for the metal equipment shed. Sign shall be red background with 1 ½" white letters and Braille. Install sign on the building exterior adjacent to door 100A. Refer also to Sheet A5.1.
- f. Provide evacuation signs in all student occupied areas. Signs shall be 8 ½" x 11". The printed copy with the evacuation routes will be provided by the Architect. The Contractor shall provide the plastic sleeve and install the signs. 10 signs are required.

2.2 Construction:

- 2.2.1 ES plastic, double layer “sand carved” engraved signs with squared corners. Colors as selected by the Owner.
- 2.2.2 Fasteners: Use screw fasteners that are non-corrosive to both the sign material and mounting surface.”

**Item No.4 Life Safety Plan – Travel Distances**

Refer to attached, revised sheet LS-1. The Travel Distances shown at the First and Second Floor Plans of Building 10 have been revised.

**Item No.5 New Doors**

- a. Refer to attached revised sheets LS-1, A2.1, A2.2, and A10.1. New doors 204A and 204B have been added at Building 10, Second Floor, Pressbox, Room 204.
- b. Specifications, Section 08710, paragraph 3.6. Add the following hardware group:

<b>HW. 08</b>			
<b>Quantity</b>	<b>Description</b>	<b>Model Number</b>	<b>Finish</b>
3	Standard Hinges	Ives 5BB1HWNRP 4-1/2" X 4-1/2"	652
1	Lockset	Corbin Russwin ML2055 LWM	626
1	Cylinder	Yale K820 1-11/16" 626 A BO 1220 VKC2	626
1	Kick Plate	Ives 8400 US32D 10" x 34"	
3	Door Silencers	Ives SR64	GRY

ADDENDUM NO. TWO

**Item No. 6 Demolition Plan**

Refer to attached, revised Sheet A2.1, Building 10.

Revise Demolition Key Note 7 pertaining to the removal of the exterior door at the existing exterior stair to read as follows:

“(7) Existing exterior door and frame to be removed. Infill with new 8” CMU. Provide paint finish each side. Refer to structural drawings.”

**Item No. 7 Handrail and Concrete Work at Buildings 9 & 10**

Refer to attached, revised Sheet A5.1. Add plan and Sections 9, 10, and 11.

**Item No. 8 General Notes**

Refer to attached, revised sheet A2.1. Add General Notes 1-11.

**Item No. 9 Addendum No. One – Trench Drain**

Change Addendum No. One, Item No. 7 to read,

“Sheet A2.2 Add the following note to Buildings 9 & 10 – Drainage & Sidewalk Plan,

Note: Trench drain shall be equal to 6 inch wide Zurn Model Z886 with P6-SDD stainless steel grate. Provide end caps and connect drain to new underground piping.”

**MECHANICAL**

**Item No. 10 HVAC Floor Plan**

Sheet M2.1. Change label of Floor Plan from Building 11 to read “Building 10”.

**ELECTRICAL**

**Item No. 11 Emergency Lighting**

Refer to attached revised Sheet E3.1. Add emergency lighting in Rooms 103, 105, and 201.

**End of Addendum No. Two**